

CYPRUS - POLIS TIS CHRYSOCHOU (TOMBS)

257

24.X.55

10. Chian jar. H. 0.705 diam. 0.314. Pl. I., second row,

enlarged detail in center, bottom row, and at top right.

The Wine Jars from Marion Tomb 104

Stamped on the upper neck with the letter alpha (Pl. I., center),

and near the toe with an incuse circle.

The twenty jars assembled on Plate I, listed as from Marion Tomb 104, with tomb numbers 1-19 and 22, range in date from the third quarter of the 5th century B.C. until at least the 1st century B.C.¹. They indicate a number of different burials; and indeed inquiries made in February 1941, three months after the tomb was opened, discovered some uncertainty about the attribution to this particular tomb of several of the jars: 13, 14, and 15, (see upper right corner of Plate I, ^{OC} top left), and possibly also either 5 or 10 (the two similar jars one above the other in the second and ^{bottom} ~~third~~ rows), may have been contributed by the police of Polis from earlier chance finds at Marion. Though I saw the tomb group as a whole, and photographed most of the stamps, early in 1941, detailed study of the jars was unfortunately postponed until January 1942, by which time all but 1-4 and 10 had been buried, as part of the Museum's air raid precautions. For all save these, present comment is based on the photographs here published, except that measurements, and any notes on the clay, derive from the Museum's inventory list. As has been remarked by Mr. Karageorghis², burial groups could not be distinguished in the tomb. The jars are presented here in chronological groups, using their inventory numbers.

I. Fifth century B.C., second half. Nos. 5, 7, 10, 18.

5. Chian jar. H. 0.805. Pl. I., bottom.

Unstamped.

Normal Chian of the type with bulging neck, latest period.

10. Chian jar. H. 0.78; diam. 0.314. See Pl. I, second row, and enlarged detail in center. tomb stand at the end of a series with Stamped on the upper neck with the letter nalphat (Pl. I, center), and near the toe with an incuse circle type here exemplified by 7. A sum Jar of the same type as 5. connection with a mid 5th century example found in a dated deposit at the Athenian Agora.⁶ A publication is planned of the Chian series as a whole.

7. Chian jar. H. 0.74. Pl. I, second row.
Unstamped.

Normal Chian of the type with straight neck and knob toe, nos. 1, 3 and 4, all shown in the second row in Pl. I, their stamps in the first three rows of Pl. II.

Unstamped.

1. Jar of 'Appodfouç, term of Τιμαρόπας, in the month

Epsv⁷. A group of jars remarkably similar to Nos. 15, c7, 10 and 18, dated by context in the third quarter of the 5th century B.C., is illustrated in Hesperia IV, 1935, p. 496, fig. 17³. The two Chian

types are represented by examples closely resembling ours, and the

two other jars, nos. 87 and 88, are each a good deal like our 18, Preserved H. 0.72; diam. 0.31. The bottom of the jar is missing, though there are distinctive features that prevent the attribution

of 18 to either of the categories they represent. Our jar has the

general proportions of 87, but the flaring sharp-edged rim of 88;

and its toe seems not to be the plain flare shown on 87 and 88, fabricant handle (see Pl. II, third row).

but to have a projecting torus edge, making it more of a knob. A

number of similar jars have been published from Cyprus, and the type perhaps derives from one of the Greek cities of the island. Note that reference is made in later times (in Ptolemaic papyri) to jars from Kourion and from Paphos⁴. A parallel from a better dated tomb in Marion serves to place 18 at least as early as the

last quarter of the 5th century.⁵; diam. 0.332. One handle and part of the neck is missing, also the tip of the jar at the bottom.

The development of the Chian jar has been fairly well established. 5 to 10 of this type stand at the end of a series with bulging neck, a type evidently replaced in the third quarter of the century by the straight-necked type here exemplified by 7.

A summary has been published in connection with a mid 5th century example found in a dated deposit at the Athenian Agora.⁶ A publication is planned of the Chian series as a whole.

2. Jar of Ἀλέξανδρος, term of the priest Τιμαγόρας, month Ηετού. Second century B.C., second half. Rhodian stamped jars, 1, 3 and 4, all shown in the second row in Pl. I, their stamps in the first three rows of Pl. II.

1. Jar of Ἀφροδίσιος, term of Τιμαγόρας, in the month Συνθετού. H. 0.81; diam. 0.332; capacity, 26,100cc (not controlled).

Stamps: a) 'Επὶ Τιμᾷ been in the fabric
γόρα
than with the eponym Συνθετού her stamp is clear, and types are known
of Ἀλέξανδρος in which the month name appears above his own.
4. Jar of Ἀφροδίσιος, term of Εύάνωρ, in the month Συνθετού. Preserved H. 0.72; diam. 0.331. The bottom of the jar is missing.
duplicate in the Benachi collection, Alexandria.

Stamps: a) 'Ε[πὶ Εύάν]ο
ρος
b) 'Αφροδίσιου

Graffito Δ to the right of the lower attachment of the fabricant handle (see Pl. II, third row).

A complete example of the type of stamp (a) is not available, but the restoration is confirmed by a number of similarly lettered types naming Εύάνωρ with other months, the eponym's name having the same arrangement.

1. Jar, unstamped. H. 0.82. Pl. I, top row.

3. Jar of uncertain fabricant, term of Ἀριστόνομος, in the month Συνθετού. Preserved H. 0.78; diam. 0.332. One handle and part of the neck is missing, also the tip of the jar at the bottom.

Stamps: a) Επίτιμος Αριστος, see recently Hesperia VIII, 1953,
τονόνου
b) Σπυρίδην, see also Hesperia Supplement A.

(For comment on these three jars assembled under II, see their
below, under III).

In the mid century B.C., not early. None of the
persons named on their stamps is named on stamped handles found at
III. First century B.C. Rhodian jars 2, 6, 8, 9, 11 and 12,
Carthage or Corinth, destroyed in the middle of the second century,
of which 2 and 9 are stamped.

or in the construction filling of the Stoa of Attalos, built at
2. Jar of Αλέξανδρος, term of the priest Τιμαγόρας,
approximately the same time. The jars mentioned are to be dated
month not identified. H. 0.805; diam. 0.308; capacity 23,250 cc
then in the second half of the century. Note that the two that
(not controlled). Pl. I, second row, right, the stamps Pl. II,
preserve the fabricant stamp are endorsed by the same fabricant.
fourth row.

Associated with the curious fact that the three eponym stamps,
Stamps: a) Επίτιμος b) Αλέξανδρος
with three different Τιμαγόραms, are each dated in the month
[?]

which is only the sixth most common month in jar stamps⁷.

The month name may have been in the fabricant stamp, rather
than with the eponym: neither stamp is clear, and types are known
their predecessors by their relative slippiness of body, and carelessness
of Αλέξανδρος in which the month name appears above his own.
manufacture, the surface being rather lumpy, and the neck and top
The top line of the eponym stamp has been read by the help of a
poorly articulated from the rather misspelled body. The handles
duplicate in the Benachi collection, Alexandria.

tend to rise to a sharper angle at the top, and to be drawn in at
their 6. Jar, unstamped. H. 0.84. Pl. I, top row. narrower
shoulder of the jar. Handles and neck tend at least for a time to

8. Jar, unstamped. H. 0.82. Pl. I, bottom row, right.
becomes shorter: compare the earlier and later jars 1 and 2 in Pl. I,

9. Jar with partly preserved rose stamp on each handle, no
names preserved. H. 0.88. Pl. I, top row; Pl. II, bottom row, for
the stamps. and perhaps the shortest necks were followed by a tendency
to lengthen out again. Such tendencies are known to be repeated in
11. Jar, unstamped. H. 0.82. Pl. I, top row.

other jar series, for example the Thasian. The jar 2 is closely
12. Jar, unstamped. H. 0.775. Pl. I, bottom row.

Part of rim missing.

Other Rhodian jars of the 1st century B.C.,
stamped and unstamped, have been published.⁸

On Rhodian stamped jars, see recently Hesperia XXII, 1953, pp. 116-128, and a few additional notes in Hesperia Supplement X (now in press). For the three jars here assembled under II, their shape places them in the 2nd century B.C., not early. None of the persons named on their stamps is named on stamped handles found at Carthage or Corinth, destroyed in the middle of the second century, or in the construction filling of the Stoa of Attalos, built at approximately the same time. The jars in section II are to be dated then in the second half of the century. Note that the two that preserve the fabricant stamp are endorsed by the same fabricant, Αφοδίσιος; and the curious fact that the three eponym stamps, with three different eonyms, are each dated in the month Σπήνετος, which is only the sixth most common month in jar stamps.⁷

Rhodian jars of the 1st century B.C. are distinguishable from their predecessors by their relative slimness of body, and careless manufacture, the surface being rather lumpy, and the neck and toe poorly articulated from the rather misshapen body. The handles tend to rise to a sharper angle at the top, and to be drawn in at their lower attachment, where they rest on the steeper narrower shoulder of the jar. Handles and neck tend at least for a time to become shorter: compare the earlier and later jars 1 and 2 in Pl. I, the right end of the second row. However, some jars which are certainly no earlier have somewhat longer neck and handles (cf. 9 in Pl. I), and perhaps the shortest necks were followed by a tendency to lengthen out again. Such tendencies are known to be repeated in other jar series, for example the Thasian.⁸ The jar 2 is closely paralleled by no. III in the development series shown in Hesperia XXII, 1953, pl. 42; and other Rhodian jars of the 1st century B.C., stamped and unstamped, have been published.⁹

The comparison suggested between jars 1 and 2 is interesting as an illustration of the recurrence of names in the Rhodian eponym list: each jar is dated by an eponym Τιμαγόπας, but the shape makes it clear they are well removed from one another in date.

On color and shape, as well as measurements, derive from the

Museo IV. Date First century B.C. to first century A.D. Nos. 13, 14 and 15, shown together in Pl. I, a top row, right. Note above, p. 300, a question on the finding-place of these jars. Given to me. No. 22 in fact is not a pointed amphora, and scarcely belongs with the rest.

13. Coan (?) jar. H. 0.85.

Double-handled jar with offsets at base of neck and at base of shoulder, and small peg toe.

17. White ware amphora with knobbed base. H. 0.55.

14. Coan (?) jar. H. 0.915.

19. Amphora with knobbed base. H. 0.465.
Like 13.

22. Red ware amphora with flat base. H. 0.47.
The publication which identified as Coan the series to which
these two jars belong illustrates ~~an example of about their period.~~
The offset at the base of the neck is characteristic of the Hellenistic jar also, but apparently the second offset, below the handles, does not occur before the second half of the 1st century B.C.¹⁰. A more extensive publication on this series is planned.

15. Roman jar. H. 0.945.

Jar with heavy flaring rim, somewhat baggy body, and long pointed toe.

A new study of Roman amphoras and their stamps is being prepared for publication, probably in Hesperia, by Elizabeth Lyding Will. In the meanwhile, we may refer to the classification established fifty years ago by Dressel, and place 15 as related to his Type 6.

(9)
Feature

(11)

For the present jar, Mrs. Will suggests a date about the middle of the 1st century B.C.¹¹

V. Of the four jars in the lower left corner of Pl. I, notes on color and shape, as well as measurements, derive from the Museum's inventory list. These jars had been reburied when my studies were made (see above), and from the photograph do not identify themselves readily with a series known to me. No. 22 in fact is not a pointed amphora, and scarcely belongs with the rest.

16. Red ware amphora with knobbed base. H. 0.62.

17. White ware amphora with knobbed base. H. 0.55.

19. Amphora with knobbed base. H. 0.465.

22. Red ware amphora with flat base. H. 0.47.

Polis (VG)

¹ I am obliged to Mr. A.H.S. Megaw and Mr. P. Dikaios for permission to publish these jars, and for the group photographs of the jars shown in Pl. I. Mr. V. Karageorghis has been kind enough to find place for this appendix to his publication of the tomb as a whole, and to check for me in Cyprus the absence of stamps on jars not studied by me in detail.

² See above, p. 000.

³ This group is part of a dated well-deposit of the Athenian Agora, published by L. Talcott, Hesperia IV, 1935, pp. 476-523.

⁴ Cf. F.M. Heichelheim, Wirtschaftsgeschichte des Altertums, Leiden, 1938, p. 472, for references.

⁵ Marion Tomb 18, no. 5: see SCE II, p. 233, where this group is dated late in the Cypro-Classic I period, i.e. before about 410 B.C. For a profile drawing of the jar, see SCE IV, fig. LXIII, no. 12.

⁶ See Hesperia XXII, 1953, p. 105, under no. 152, for the summary, and pl. 39, no. 150, for the mid-5th century Chian jar.


⁷ See M. Nilsson, Timbres Amphoriques de Lindos, Copenhagen, 1909, p. 127, note 1. This book remains the indispensable handbook for anyone wishing to publish Rhodian stamps.

⁸ G.H. McFadden, AJA L, 1946, p. 471, fig. 13, nos. 17, 18; p. 478, figs. 14 and 15, nos. 56-63. Cf. also Classical Journal, ^{XLII} LVI, 1947, p. 448, figs. 5 and 6. The jars in both publications derive from tombs in the cemetery of Ayios Ermogenis at Curium, Cyprus, some

are stamped. An unstamped Rhodian from the Antikythera wreck (see below, note 11) is published in Eph. 1902, pl. H, no. 2.

⁹ A. Maiuri, Nuova Silloge Epigrafica di Rodi e Cos, Firenze, 1925, p. 246

10 The distinct ledge at the base of the shoulder, visible in the fragments from the deposit of 50 B.C. - 50 A.D. at Arikamedu (see Ancient India 2, 1946, p. 42, fig. 9, nos. 56 and probably also 53) is hinted at by a shallow double curve, with concave part below, in the shoulder profile of Agora P 11880, from a deposit shortly to be published by H. S. Robinson, his Group F, which he dates ca. 75-25 B.C. No such profile is found on the shoulder of the double-handled jars from the Antikythera wreck (cf. Eph. 1902, pl. H, no. 3) but only a sagging line. The wreck is considered to have taken place about 60 B.C., cf.



Stamp on 10 1:1



19 22 17 16 5 12 8



1 a



1 b



4 a



4 b



3 a



4, Graffito



2 a



2 b



9 a



9 b



4-6



5-6

Plate viii pl.

1 + 1 [6.01]

7.III.55

5.VII.55

double

24. X. 55

The Wine Jars from Marium Tomb 104

The twenty jars assembled on Plate 1, listed as from Marium Tomb 104, with tomb numbers 1-19 and 22, range in date from the third quarter of the 5th century B.C. (5, 7, and 10) to probably the 1st century after Christ. (15). They thus indicate a number of different burials; and indeed notes taken in February 1941, inquiries made three months after the tomb was opened, discovered some uncertainty about the attribution to this particular tomb of several of the jars: 13, 14, (see upper right corner of Plate) and 15, and possibly also either 5 or 10 (the two similar jars in the one above the other in the second and third rows), may have been contributed by the police of Polis from earlier chance finds at Marium. Myxistixsixstixxixxxjxx and photographed most of the stamps, unfortunately postponed until Though I saw the tomb group as a whole early time, in 1941, detailed study of the jars was unfortunately postponed until January 1942, by which time all but 1-4 and 10 had been buried, as part of the Museum's air raid precautions. For all save these, present comment is based chiefly on the photographs here published, except that measurements, and any notes on the clay, derive from the Museum's inventory list. As has been remarked by Mr. Karageorghis, burial groups could not be distinguished in the tomb. The jars are presented here in chronological groups, using their inventory numbers.

1. Fifth century B.C., second half.

I. Fifth century B.C., second half. Nos. 5, 7, 10, 18.

5. Chian jar. ~~XXXI~~ H. 0.805. Pl. I, bottom.

~~Unstamped, so far as I know.~~

Normal Chian ~~marks~~ of the type, with bulging neck, latest period. ♂

10. Chian jar. H. 0.78; ~~xxxixxxxxx~~ diam. 0.314. Pl.I, second row, and enlarged detail in center.

(Pl.I, center)

Stamped on the upper neck with the letter alpha, and near the toe with an incuse circle.

Jar of the same type as 5.

7. Chian jar. H. 0.74. Pl.I, second row.

~~Unstamped so far as I know.~~

Normal Chian of the type with straight neck and knob toe.

18. Jar. H. 0.55. Pl.I, top left.

~~Unstamped so far as I know.~~

A ~~remarkably similar~~ group of jars, dated by context in the third quarter of the fifth century B.C., is illustrated in Hesperia IV, 1935, p. 496, fig. 17. [3]

The two Chian types are represented by examples closely resembling ours, and the two other jars, nos. 87 and 88, are ^{each} a good deal like our 18, though there are distinctive features that prevent the attribution of 18 to either of the categories they represent. Our jar has the general proportions of 87, but the flaring sharp-edged rim of 88; and its toe seems not to be the plain flare shown on 87 and 88,

Forms
but to have a projecting edge, making it more of a knob. A number of similar jars

have been published from Cyprus, and the type ~~is~~ perhaps derives from one of the

Note that Ptolemaic
Greek cities of Cyprus. Reference is made in later times (in papyri) to jars
(This island.)

from Kourion and from Paphos. A parallel from a better dated tomb in Marion serves

to place 18 at least as early as the last quarter of the ^{fifth} century. [5]

The development of the Chian jar has been fairly well established. 5 and 10

of this tomb stand at the end of a series with bulging neck, a type evidently

replaced in the third quarter of the century by the straight-necked type here

exemplified by 7. A summary has been published in connection with a mid fifth

century example found in a dated deposit at the Athenian Agora. [6] A publication

is planned of the Chian series as a whole.

II. Second century B.C., second half. Rhodian stamped jars, 1, 3 and 4,

all shown in the second row in Pl.I, their stamps in the first three rows of Pl.II.

1. Jar of ΑΦΡΟΔΙΣΙΟΣ; term of ΤΙΜΑΓΟΡΑΣ, in the month ΣΜΙΝΘΙΟΣ. H. 0.81;

diam. ~~0.331~~ 0.332; capacity, 26,100 (not controlled).

Stamps: a) ΕΠΙ ΤΙΜΑ
ΓΟΡΑ
ΣΜΙΝΘΙΟΥ

b) ΑΦΡΟΔΙΣΙΟΥ

4

2. Jar of ΑΦΡΟΔΙΣΙΟΣ, term of ΕΥΑΝΩΡ, in the month ΣΜΙΝΘΙΟΣ. ~~XXXIX~~ Preserved

H. 0.72; diam. 0.331. The bottom of the jar is missing.

are suitable to column 1, don't see from it getting excessive, though a good deal of due

Dear Lucy,
There are two proofs of Figure 6. Yours still timely.
~~a grid is too small & therefore would be much~~
~~criticized if we print it this way, then trouble is in~~
~~the relative size of grid and crosses: that's expected~~

~~large type & brush patterns, but actually the~~
~~one appears in full vision as slightly less~~
~~high than the crosses will fit into the~~
~~page margin, being a little less in height than the~~

~~small-scale crosses, so I suggest a very large~~
~~crosses~~
~~suggest the relation in size~~

I guess I can

~~forget also that they would be placed below the~~
~~line, which would tend to remain as~~

grids. This will all be better prepared with
you now that I see what happens and why,

and now that I fully understand why black-

grid paper does not appeal commercially. (Because

one more wants all to construct a grid & appear

in the first drawing; so this one would have

been made ~~less~~ ^{less} difficult if the ~~black~~ ^{white} paper had

and left ~~black~~ ^{white} intervening space line of

squares had been omitted (as H.A.T. notes); ~~but~~ if the

lines had been printed and the names without being

wound, no doubt the ~~print~~ ^{Marines} would have pasted

the names ~~to~~ without covering the lines.

Stamps: a) Ε[ΙΙ] ΕΥΑΝ]Ο
ΠΟΣ
ΣΜΙΝΘΙΟΥ

b) ΑΦΡΟΔΙΣΙΟΥ

Graffito Δ to the right of the lower attachment of the fabricant handle

(see Pl.II, third row).

A complete example of the type of stamp (a) is not available, but the
similarly lettered
restoration is confirmed by a number of types naming ΕΥΑΝΩΡ with other months,
the eponym's name having
~~in~~ the same arrangement.

3. Jar of uncertain fabricant, term of ΑΡΙΣΤΟΝΟΜΟΣ, in the month ΣΜΙΝΘΙΟΣ.

Preserved H. 0.78; diam. 0.332. One handle and part of the neck is missing, also
the tip of the jar at the bottom.

Stamp: a) ΕΙΙΙ ΑΡΙΣΤΟΝΟ
ΤΟΝΟΜΟΥ
ΣΜΙΝΘΙΟΥ

b) missing

(For comment on these three jars assembled under II, see below, under III.)

III. First century B.C. Rhodian jars 2, 6, 8, 9, 11, and 12, of which 2
and 9 are stamped.

2. Jar of ΑΛΕΞΑΝΔΡΟΣ, term of the priest ΤΙΜΑΓΟΡΑΣ, month not identified.

H. 0.805; diam. 0.308; capacity 23,250 cc (not controlled). Pl.I, second row, right,
the stamps Pl.II, fourth row.

Stamps: a) ΕΙΙ' ΙΕΡΕΩΣ
ΤΙΜΑΓΟΡΑ
[?]

b) ΧΑΣΣ ΑΛ[Ε]ΞΑΝΔΡΟ[Υ]

P) APPROXIMATE

MAYA III (a) : questi
SOY
YOLIMARoll

333

elbow joint is to be bent and the right end of A will be

1) Ans 1 ^a nota ^a 2)

1 | 2 | 3

(not brist II.II sea)

2) Ans 3 ^a nota ^a 2) ^a
(6x9)

24 - 27 - 28 - 30 - 31

gated area a'wado e'd
transmitter area ord a'statiarea, which is about 1000000 m², consists mainly of soil.

Soil, which is poor and has a low water content, is mainly sand, silt and clay.

yolima (a

MAYA III (a) : questi

YOLIMA

YOLIMA

(III year : wold see, it rains hard and wind could move no plants yet.)

Sandy loam, 5%坡度, 15.8% S, 8.8% sand, 30.0% silt, 31.1%

The soil is yellowish brown and has a high content of organic matter.

Boulders are 8 mm

Soil texture diagram, RADIANT series, is the same as YOLIMA to 1000 m.

Soil texture diagram, RADIANT series, is the same as YOLIMA to 1000 m.

Soil texture diagram, RADIANT series, is the same as YOLIMA to 1000 m.

YOLIMA (a)

MAYA III (a) : questi

YOLIMA

name

The month may possibly have been in the fabricant stamp, rather than with the eponym: neither stamp is clear, and types are known of ΑΛΕΞΑΝΔΡΟΣ in which the month name appears above his own. The top line of the eponym stamp has been ~~fix~~ read by the help of a duplicate in the Benachi collection, Alexandria.

6. ~~ΗΜΙΧΩΡΑ~~ Jar, apparently unstamped. H. 0.84. Pl.I, top row.

8. Jar, ~~apparently~~ unstamped. H. 0.82. Pl.I, bottom row, infix right.

9. Jar with partly preserved rose stamp on each handle, no names preserved.

H. 0.88. Pl.I, top row; Pl.II, bottom row, for the stamps.

11. Jar, ~~apparently~~ unstamped. H. 0.82. Pl.I, top row.

12. Jar, ~~apparently~~ unstamped. H. 0.775. Pl.I, bottom row.

Part of rim missing.

On Rhodian stamped jars, see recently Hesperia XXII, 1953, pp.116-128, and

a few additional notes in Hesperia Supplement X (now in press). For the three jars

here assembled under II, their shape places them in the second century B.C., not

early. None of the persons named on their stamps is named on handles found at

Carthage or Corinth, destroyed in the middle of the second century, or in the con-

struction filling of the Stoa of Attalos, built at approximately the same time.

in section II

The jars are to be dated then in the second half of the century. Note that the

two ~~JARS~~ that preserve the fabricant stamp are endorsed by the same fabricant,

ΑΦΡΟΔΙΣΙΟΣ; and the curious fact that the three eponym stamps, with three different

eponyms, are each dated in the month ΣΕΠΤΕΜΒΡΙΟΣ, which is only the sixth most common

month in jar stamps.

emsn

Athens 14. June 1955

With most respect, you will find out we need some time to make a good
choice among the many we have received; we have not
had time to go through all the material yet.

Dear Mr. Benaki

Since Miss Gais wrote to you, we have received your letters

~~52 - 61 (Letter 48 has been received)~~ Unfortunately I was not
able to mark your Kuidian rubbings with KT numbers
for a long time, and I understand that this ~~is because~~
~~makes~~ of too much trouble for you in the Apothecary.

Today I am sending you back 1) Kuidian rubbings, after
marking with KT numbers, received with letters 45
49-50 and 52. As you will see there are new types for
our files, and for your collection. On the sheet of rubbings
received with letter 45, 3 V. 55 ~~I think you have two pieces~~
~~from the same handle. I marked them KT 2119~~

KT 2119 ABC 1 and KT 2119 ABC 2 but I think they
are two pieces of the same handle. Are not they?

2) A sheet of new early Rhodian, received w. letters 49-50
brought by Miss Shier. On the rubbings you will find
my readings. There is a new Rhodian name ^{name} ~~Kakw~~
Please, how many handles in your collection have
been marked in February with KT 491? Can you
give ABC numbers to some of this type included in
letters 49-50 and 52?

3) Loan rubbings ABC 722 - 728

4) A duplicate of numbered readings of LK ABC 372-373,
made from rubbings.

M^r Koundis is ~~fall the summer~~ ^{in Rhodes} but I do not
know what ~~part~~ ^{most} of the season Rhodes is crowded
by tourists.

Sincerely yours

Rhodian jars of the 1st century B.C. are distinguishable from their predecessors by their relative slimness of body, and careless manufacture, the surface being rather lumpy, and the neck and toe ~~especially~~ misshapen poorly articulated from the rather misshapen body. The handles tend to ~~especially~~ rise to a sharper angle at the top, and to be drawn in at their lower attachment, where they rest at least for a time on the steeper narrower shoulder of the jar. Handles and neck tend to become earlier and later shorter: compare the two jars 1 and 2 in Pl. I, the right end of the second row, which are certainly no earlier. However, some jars to be dated in all probability also in the 1st century have somewhat longer neck and handles (cf. 9 in Pl. I), and perhaps the short necks were followed by a tendency to lengthen out again. Such tendencies are known to be repeated ~~them~~ in other jar series, for example the Thasian. The jar 2 is closely paralleled by ~~the~~ no. III in the development series shown in Hesperia XXII, 1953, pl. 42; and other Rhodian jars of the 1st century B.C., stamped and unstamped, have been published. []

The comparison suggested between jars 1 and 2 is interesting as an illustration of the recurrence of names in the Rhodian eponym list: both jars are dated by an eponym ΤΙΜΑΓΟΡΑΣ, but the shape makes it clear they are removed from one another in date.

From March 4-5, 1953.

most work oldskim singgahat was 0.7 yards far out to sea. (prob.)
Miscellaneous from M.S.B.F. (?)

~~edit, consideration of factors for all samples mentioned by consecution.)~~

group xanthopelagic fish and benthic bottom trawl used mostly

Haploblepharus

regularly seen in bottom trawl gear. Found in

unidentified specimens of were obtained off . ybcd regulars render odd north California

Acanthopagrus bow

in

bowcase

near you. A few species found to be part of benthic net odd to benthic

odd a lot near the S.S. MS

Kazunobius

MS

odd to benthic bottom trawl . MS odd to benthic bottom trawl odd no

total benthic trawl

not benthic odd to the right off . 1.5 mi S of San Fran and odd enough ; probably

bottom trawl odd to benthic

over species odd at sea odd to benthic odd to benthic

bottom

abundance odd to benthic benthic (1.5 mi S) odd benthic odd to benthic

odd to benthic odd to benthic odd to benthic odd to benthic

odd to benthic odd to benthic odd to benthic odd to benthic

bottom

odd to benthic odd to benthic odd to benthic odd to benthic

bottom

odd to benthic odd to benthic odd to benthic odd to benthic

bottom

odd to benthic odd to benthic odd to benthic odd to benthic

bottom

odd to benthic odd to benthic odd to benthic odd to benthic

bottom

odd to benthic odd to benthic odd to benthic odd to benthic

bottom

odd to benthic odd to benthic odd to benthic odd to benthic

bottom

odd to benthic odd to benthic odd to benthic odd to benthic

bottom

odd to benthic odd to benthic odd to benthic odd to benthic

bottom

odd to benthic odd to benthic odd to benthic odd to benthic

bottom

odd to

IV. Late first century B.C. to first century A.D. Nos. 13, 14, and 15,

shown together in Pl. I, top row, right. Note above, p. 000, a question on the finding-place of these jars.

13. ~~xxxxxx~~ Coan(?) jar. H. 0.85

Double-handled jar with offsets at base of neck and at base of shoulder, and small peg toe.

14. Coan(?) jar. H. 0.915.

Like 13.

The publication which identified ~~this~~ as Coan the series to which these two jars belong illustrates an example of about their period. [9] The offset at the base of the neck is characteristic of the Hellenistic jar also, but apparently the second offset, below the handles, does not occur before the middle of the 1st century B.C. A more extensive publication on this series is planned.

15. Roman jar. H. 0.945

Jar with heavy flaring rim, ^{conical} baggy body, and long pointed toe.

A new ~~publication~~^{study} of Roman amphoras and their stamps is being prepared for publication, probably in Hesperia, by Elizabeth Lyding Will. In the meanwhile,

we may refer to the classification established fifty years ago by Dressel, and place 15 as ~~an example of his Type 6,~~ ^{For the present} ~~dateable in the late 1st century B.C. to early 1st~~ century after Christ. [11] ^{middle of 1st and 2nd cent. B.C.}

9. V. 1951 6.12

- 7 -


Analysis of MSBF & made

and in holtup a 000 kg over a year. Not got 1.5% of copper made

To be made in various categories separately.

Begins after Production of (a) 2000 kg of MSBF

This will take time to be done so need to start at earliest when it begins



6.13

V. Of the four jars in the lower left corner of Pl.I, notes on ~~color~~ and color
shape, as well as measurements, derive from the Museum's inventory list. These
jars had been reburied when my studies were made (see above), and from the photo-
graph do not identify themselves readily with a series known to me. No.22 in fact
is not a pointed amphora, and scarcely belongs with the rest.

16. Red ware amphora with knobbed base. H. 0.62.

17. White ware amphora with knobbed base. H. 0.55.

19. Amphora with knobbed base. H. 0.465.

22. Red ware amphora with flat base. H. 0.47.

1

I am obliged to Mr. A.H.H.S. Megaw and Mr. P. Dikaios for permission to publish these jars, and for the group photographs of the jars shown in Pl.I.

Mr. V. Karageorghis has been kind enough to find place for this appendix to his publications of the Tomb as a whole, and to check for me in Cyprus the absence of stamps on jars not studied by me in detail.

2

See above, p.000.

3

This group is part of a dated well-deposit of the Athenian Agora, published by L.Talcott, Hesperia IV, pp.476-523.

4

Cf. F.M. Heichelheim, Wirtschaftsgeschichte des Altertums, Leiden, 1938, p.472, for references.

5

SCE
Marion Tomb 18, no.5: see SCE II, p.233, where this group is dated ~~at~~ late in the Cypro-Classical I period, i.e. before about 410 B.C. For a profile drawing of the jar, see SCE IV, fig. LXIII, no.12.

6

See Hesperia XXII, 1953, p.105, under no.152, for the summary, and pl.39, no. 150, for the mid-fifth century Chian jar.

7

See M.Nilsson, Timbres Amphoriques de Lindos, Copenhagen, 1909, p.127, note 1.

This book remains the indispensable handbook for anyone wishing to publish Rhodian stamps.

8

G.H.McFadden, AJA L, 1946, p.471, fig. 13, nos.17,18; p.478, figs.14 and 15, nos. 56-63. Cf. also Classical Journal, XLIII, 1947, p.448, fig.5 and 6. The jars in both publications derive from tombs in the cemetery of Ayios Ermoyenis at Curium, Cyprus, some are stamped. An unstamped Rhodian from the Antikythera wreck (see below, note 11) is published in EΦ. 1902, pl.H, no.2.

9

A.Maiuri, Nuova Silloge Epigrafica di Rodi e Cos, Firenze, 1925, p.246.

c 10

The distinct ledge at the base of the shoulder, visible in the fragments from the deposit of 50 B.C. - 50 A.D. at Arikamedu (India see Ancient India 2, 1946, p.42, fig.9, nos. 56 and probably also 53) is hinted at by a shallow double curve, with concave part below, in the shoulder profile of Agora P 11880, from a deposit shortly to be published by H.S.Robinson, his Group F, which he dates ca. 75-25 B.C.

the shoulder of
No such profile is found on the double-handled jars from the Antikythera wreck
(cf.EΦ. 1902, pl.H, no.3) but only a sagging line. The group from the wreck is

6.17

12. VV, 55


considered to have taken place about 60 B.C., cf.

11
CIL XV

~~PLATE~~ PLATE



18 7 6 4 9 11 3 10 15 1 2




Stamp on 10 11





19 22 17 16 5 12 8

7.01



1 2 3 4 5 6

7.02





1a



1b



4a




4b



3a




4, Graffito




2a



2b



9a



9b

2. II. 75 [8]

(manus.)
Publication of Polis Tomb 104

I don't find a note on what happened about this publication ^{for} which I had prepared the amphoras in 1955, see ms. in this folder. But I have a good recollection that it was decided that the full publication prepared by Karagiannis, and by me for the appendage on the amphoras, would be abandoned for the foreseeable future, and one of these lists would be published in a report by the Dept. of Antiquities. I have a vague recollection of this summary list publication as having been made, but seem to have no copy of same. Last letter this is from Vasos, date 20. XII. [56], saying publ. of our joint paper would be delayed.

All this now in connection with inquiry by ELW about whether I had published a SPE amphora from this tomb -

[See a ROMAN folder my letter of 4. IV. 75
& ELW.]

CYPRUS

27. III. 73 [9]

POLIS TIS CHRYSOCHOU

Cyprus: Polis Tis Chrysochou Tomb 61 II
(in hands, but in mounting base)

Non-joining pair found by Dr. Börker in the
Berlin Museum TJ 8161 B } with a chain
... ... C } by the same hands,
that of Schafstad - Richter. (also in Tomb, no. 9) KT 320 IV TB

a.) Επιτάφιος αριστερός ώμος
Δαδίου

b.) Εύκλειτος
casual right

Non-joining pair.
Combination based on closely similar clay,
and shape, (including pressure of thumb and index,
shape of neck looks identical.) of two hands
found in the same tomb.

Now:

Cyprus: Polis Tis Chrysochou, Tomb 61, II,
now in Berlin Museum. Information
from Ch. Börker, III. 73.

10.01

for nearly two months. I am writing to you to Cypriot Museum

Nicosia, 20/2 [1955]

Dear Mrs Grace,

I must apologize for the long delay in answering your letters. I thank you very much for the appendix. I waited for so long because I expected that the jars would have been unburied in the meantime and I would have been able to answer your points. Unfortunately they are still there and they will be for some time until we build a new store-room. There is absolutely no space for anything more in the Students' Galleries.

I have no idea when the 'Report' is coming out. It has not yet gone to the printers. We better wait a bit more to see how the situation will develop. The ^{Government} printers at present are busy doing other things and would not even think of printing museum reports!

I have ordered other photographs of the jars and will send them to you as soon as I can. Mr. Halloulli, our photograph, is back from Larnaca where he has been with the Director.

10.02

for nearly two months.

[Received, with Nicissia cancellation
of 28. XII. 55, May 1958; leave been
attached to back of plate.]

I really regret that things are as they are now. But in our Museum and Department Hellenistic pottery is overshadowed by the more 'important' things. I hope that you will forgive this delay. One day the 'Report' will and must come out. Let us be patient.

With kindest regards,

Yours very
Managing

11

American School of Classical Studies
Athens, Greece December 14, 1955

Mr. Vassos Karageorghis
Department of Antiquities
Nicosia, Cyprus

Dear Mr. Karageorghis:

I wrote to you on July 5, by hand of Miss Frances Jones, on the subject of the appendix on jars from Marion Tomb 104. As you were not then in Cyprus, Mr. Megaw sent the letter back to me. I hope that you have since received it, together with the two mounted plates which Mr. Megaw was kind enough to take back to Cyprus when he came through here in October.

I enclose here the text and footnotes for the appendix. Note that I am assuming that you will state in the text, as you did in writing to me, that burials could not be distinguished - see my note 2, which will need a page reference to your text. Note also, of my note 1, that I am hoping you will be kind enough to look at the jars which I call "unstamped" in my text (e.g. p.2, no.7), and see if any of them actually has a stamp.

Please let me know whether you have received my letter of last July 5, as there are several points in it which I will not repeat here.

I should like to know when this is likely to be given to the printer, in case there are some revisions to be made, if much time is to go by. I have not been able to find the discussion I want about the date of the Antikythera wreck (something recent, possibly not published); and there may be other things.

My best greetings to you and to Mr. Megaw and Mr. Bikaios, and other friends in the Service.

Yours sincerely,

Kindness of Mr. and Mrs. Catling.

ANTIQUITIES DEPARTMENT, NICOSIA, CYPRUS

6/9/55

Dear Virginia

many thanks for yours
by hand of Francis Jones. As
Kerayaphinis is now in England
and as we shall not be working
on his Ptoleis plates ~~at~~ before that
winter, I think I should let you
have ~~them~~ back the 2 plates + letter
you sent him. We shall look
forward to seeing them again at a
later date - perhaps with the short
text you will write to go with them.

It will be long before you
get this, but if we have a
chance while at the Piraeus in
a few days time we shall do our
best to see you.

Yours

Peter.

Athens, July 5, 1955

Dear Peter,

I was glad to hear from Elektra's mother that you have a holiday for England and Ireland this summer. I may possibly come up myself. The last time I called at Alopekis Street, I was told Mrs. Mangoletsy had left, so perhaps Elektra has gone on ahead of you.

I'm not sure where Mr. Karageorghis is at present, either in person or in preparing his publication, so I would be glad if you would cast an eye over the communication Franny is bringing for him from me. To ~~put~~ prepare the text I have in mind will only be a matter of a few days. If he does not want it now, would he or you be so good as to return me the plates? Franny Jones would I think be willing to bring them back.

I do hope that we shall see something of you and/or Elektra coming if not going.

Yours,

American School of Classical Studies
Athens, Greece
July 5, 1955

Mr. Vassos Karageorghis
Department of Antiquities
Nicosia, Cyprus

Dear Mr. Karageorghis:

Miss Frances Jones is kind enough to bring you this letter with the enclosed two plates proposed as illustration of a short piece of text I shall send you for the publication of the wine jars from Marium Tomb 104, if you would like to have it. I refer to your letter to me of last January 15, and regret that my absence in Egypt, and then great pressure of work, has delayed this response. I do not know in the meanwhile what stage you have reached in your publication. Will you please let me know whether you now have place for these two plates, plus several pages of text on the provenance, date, etc. of the jars, and some detail on the stamps? I am supposing that the format of your publication will be that of Tsambres and Aphendrika in the Report 1937-1939, i.e. size of plates, etc. The plates as I have mounted them mustn't be reduced, because the stamps are at actual size. If they won't fit, please send them back to me for alteration. The captions should run about as follows:

Plate 1. Marium Tomb 104. Wine Jars.

Plate 2. Marium Tomb 104. Stamps and a Graffito on Rhodian Jars. 1:1.
Of course, adjusted so the style fits that adopted for the rest of the publication. Numbers written on the plates in pencil, please have them printed.

I should be grateful if you would send me second prints of the two photographs of the jars in groups, because now I have placed them in Plate 1, I have no copy for my files nor to finish properly the investigation of several of the jars which I know only in these photographs, as they had been reburied. If you now cannot use my contribution, do you mind if I publish it somewhere else?

Yours sincerely,

Tel. No. :

GOVERNMENT

OF CYPRUS



Our Ref. :

50/38/2.

Your Ref. :

DEPARTMENT OF ANTIQUITIES
NICOSIA

15th January, 1955.

Dear Miss Grace,

I have almost completed the compilation of the inventory of Marium tombs 104 and 105 (formerly 1A and 1B) and I have left the Amphoras for you as we agreed when I was at Athens. Unfortunately the tomb was very much disturbed before being excavated and no distinct burials can be identified from the report and the plan prepared at that time. The objects range chronologically from the 5th century B.C. to the 1st century A.D. I do not know about the Amphoras. Perhaps you might also add a few words on the amorphiskoi of variegated glass.

I think there are three ~~another~~ tombs from Larnaca which you were proposing to publish. I would be most grateful if you would like to do the amphoras against ~~the~~ (or the whole group); the tombs are from the site "Dasos tis Alikis" (Salt Lake Forest) I will supply any information or photographs if you want them.

Thanking you in advance,

Yours sincerely,

(Vassos Karageorghis)

Miss Virginia Grace
American School of Classical
Studies.

cover letter
Mr. Raugh & his

16

Plate nos.

"now in press"

nos 2

A

17.01

21. VI. 48

Note phenomenon:

The writer names
of the 3 cases from this
lens which it is present,
is in every case
2 species
which is only the 6th most
common of the 12 moss.
in N's list.

17.02

Conical amphora, wide base. Knobbed base. H. 66 cm.
Conical amphora. H. 65 cm.

-1-

19. Conical CATALOGUE OF OBJECTS OF THE TOMBS EXCAVATED

20. Bobbin-shaped AT POLIS TIS CHRYSOCHOUS "TIPOZITA"

21. Conical amphora. H. 28 cm. Handles from neck to shoulder. Date 8/12/40.

22. Red ware amphora with flat base and cylindrical neck, handles
Tomb 1 A.

"See file 154/36.
Sl. 188, 187, 186
R. (2. No. 1330)

1. Nearly conical amphora with knobbed base, stamped handles from
neck to shoulder. H. 77 cm. ϕ I, L

2. Bobbin-shaped amphora with knobbed base, stamped handles from
neck to shoulder, tall cylindrical neck. H. 82 cm. ϕ I, L

3. Amphora as No. 1. One handle missing. H. 79 cm. ϕ I, L

4. " " " Base broken. H. 72 cm. ϕ I, L

5. Conical amphora with swollen rim, knobbed base, handles from
neck to shoulder. H. 80,5 cm. ϕ II

6. Bobbin-shaped amphora with knobbed base, handles from neck to
shoulder. H. 84 cm. ϕ I a,

7. Conical amphora as No. 6. H. 74 cm. ϕ II

8. Bobbin-shaped amphora with knobbed base, handles from rim to
shoulder, tall cylindrical neck. H. 82 cm. ϕ II

9. Bobbin-shaped amphora as No. 8. H. 88. ϕ II from rim to

10. Conical amphora as No. 11. Stamped A near rim. H. 78 cm. ϕ I, L

11. Bobbin-shaped amphora. H. 82 cm. ϕ II

12. Bobbin-shaped amphora with knobbed base, handles from neck to
shoulder. Part of rim missing. H. 77,5 cm. ϕ II

13. Bobbin-shaped amphora with conical shoulder and double handles H. 82 cm.
H. 85 cm. ϕ II

14. Bobbin-shaped amphora as No 13. H. 91,5 cm. ϕ I, R

15. Plain white ware amphora with tall pointed base, tall cylindrical
neck. H. 94,5 cm. ϕ II

16. Ovoid red ware amphora with knobbed base. H. 62 cm. ϕ II

ME. 10
with
25.11.20.
17.4.10
prob
(14.6.58)
62

17. Ovoid amphora, white ware. Knobbed base. H 55 cm. from ~~base~~^{neck} to
 18. Conical amphora. H 55 cm. ϕ I a, 1
19. Conical amphora with knobbed base. H 46,5 cm. ϕ II
20. Bobbin-shaped amphora. H 28,5 cm. Handle missing. H 12,5 cm.
21. Conical amphora. H 28 cm. pinched ~~handles~~ handles from near rim to
 22. Red ware amphora with flat base and cylindrical neck, handles
 23. Low from neck to shoulder. H 47 cm. ϕ II
24. Red ware amphora with rounded base, wide rim. Handles from rim
 to shoulder, incised lines round shoulder. H 26 cm.
25. White ware amphora with base-ring horizontal handles. One handle
 missing, double rim. H 25 cm. shoulder. H 22,5 cm.
26. Red ware amphora with rounded base, wide rim, vertical handles
 from rim to shoulder. H 20,5 cm.
27. Amphora as No. 25. H 16 cm.
28. White ware jug with base-ring, narrow neck with a wide spreading
 rim handle from neck to shoulder. Flat handle H 34 cm.
29. White ware jug with base-ring handle from rim to shoulder.
 Wide neck. H 35,5 cm. No 46. H 23 cm.
30. Jug as No. 28. H 29,5 cm.
31. " " " 29. H 29,5 cm.
32. Red ware jug with flat base, wide neck handle from rim to
 shoulder H 20 cm.
33. Spindle-shaped bottle as No 46. H 23 cm.
34. Red ware jug with flat base, wide neck handle from rim to
 shoulder H 20 cm.
35. Spindle-shaped bottle as No 46. H 23 cm.
36. Red ware jug with base-ring narrow neck & handle from neck to
 shoulder. Flat rim. H 22,5 cm.
37. Red ware conical shaped jug with base-ring narrow neck, part
 of rim missing. H 19 cm.
38. Red ware amphora with flat shoulder, base-ring narrow tall
 neck handle from neck to shoulder. H 17 cm. H 10,5 cm.
39. Black slip jug with base-ring handle from neck to shoulder,
 part of rim missing. H 20,5 cm.
40. Ovoid bottle as No 38 with brown slip covering the upper part
 of neck. H 10 cm.

37. Jug with base-ring tall narrow neck flat handle from neck to shoulder. H 16,5 cm.
38. Jug as No 34 H 16 cm.
39. Jug with wide rim, rounded base. Handle missing. H 12,5 cm.
40. Small jug with base-ring pinched lip handles from near rim to shoulder. H 12,3 cm.
41. Lower part of a base full of plaster.
42. Red slip jug conical body narrow tall neck handle from neck to shoulder. Spreading mouth. H 38,5 cm.
43. Red washed jug with base-ring flat shoulder tall narrow neck flat handle from neck to shoulder. H 22,5 cm.
44. Yellowish ware jug with base-ring narrow neck handle from neck to shoulder. H 12,5 cm. *The inside part is covered.*
45. Plain grey ware spindle-shaped bottle, broad rim, tall narrow neck, ovoid body. H 27 cm.
46. Plain white ware spindle-shaped bottle, broad rim, tall narrow neck, ovoid body. H 25 cm.
47. Spindle-shaped bottle as No 46. H 23 cm.
48. Spindle-shaped bottle as No 46 H 23 cm.
49. Spindle-shaped bottle as No 46. H 23 cm.
50. Spindle shaped bottle as No 46. H 21,5 cm.
51. Spindle-shaped bottle as No 50 with spreading mouth H 21,5 cm. *Red slip covers the inside part of the*
52. Spindleshaped bottle as No 50 H 19 cm.
53. Spindle bottle. H 15,5 cm.
54. Spindle bottle. H 9,5 cm. *The bowl is covered with red slip.*
55. Spindle-shaped bottle. H 14 cm.
56. Ovoid bottle with base-ring. H 10 cm. *Brown slip covers the inside part.*
57. Black ware ovoid ~~bottle~~ with base-ring. H 10,5 cm.
58. Ovoid bottle with flat base, red slip covers the upper part of neck. H 15 cm. *Red slip covers the inside part. H 17 cm.*
59. Ovoid bottle as No 58 with brown slip covering the upper part of neck. H 15 cm.

89. Plain white ware bowl with flat base. D 16 cm.
60. Ovoid bottle as No 58 H 15,5 cm.
61. Ovoid bottle as No 58. Black slip covers the upper part of neck
H 14 cm.
62. Plain bowl with flat base. D 15,5 cm.
63. Ovoid bottle as No 61. H 12,5 cm.
64. Ovoid bottle as No 61 Part of lip missing. H 12 cm.
65. Plain white ware ovoid bottle H 12 cm.
66. Ovoid bottle, neck covered with red slip. H 10 cm.
67. Ovoid bottle as No 66. Neck covered with red slip. H 9,5 cm.
68. Plain bottle. H 10,5 cm.
69. Shallow conical bowl with base-ring. The inside part is covered
with red slip. D 23 cm.
70. Bowl as No 69 D 20 cm.
71. " " " " D 18 "
72. Red washed ware bowl with moulding round middle. D 10,5 cm.
73. Bowl as No 99. D 10,5 cm.
74. Bowl covered with brown slip in the inside part. D 17,5 cm.
75. Bowl as No 74. D 17,5 cm.
76. Hemispherical red washed bowl with base-ring. D 9,5 cm.
77. Bowl as No 102. Part of rim missing. D 9 cm.
78. Bowl with flat base. Red slip covers the inside part of the
106. Red bowl. D 18 cm. parallel horizontal lines on base.
79. Bowl as No 74. D 17,5 cm.
80. Conical bowl with base-ring. The bowl is covered with red slip.
109. Red bowl. D 18,5 cm. flat rim decorated with incised strokes. D 16,5
81. Conical bowl. The inside ~~xxxx~~ part is covered with brown slip.
111. Red bowl. D 17 cm. late. D 14,5 cm.
82. Bowl as No 69. D 17 cm. decorated with vertical dotted lines in
83. Bowl with flat base. Red slip covers the inside part. D 17 cm.
84. Bowl as No 74. D 17 cm.

85. Plain white ware bowl with flat base. D 18 cm.
86. Red washed cover with knob conical shape D 19 cm.
87. Plain conical bowl with flat base. D 17,5 cm.
88. Plain bowl with flat base. D 15 cm.
89. Plain bowl with flat base. D 13,5 cm.
90. Plain bowl with flat base. D 12,5 cm.
91. Plain bowl with flat base. D 13 cm.
92. Plain bowl with flat base. D 13 cm.
93. Plain bowl with flat base. D 12,5 cm.
94. Bowl as No. 93. D 13,5 cm.
95. Bowl as No. 93. D 13,5 cm.
96. Plain bowl, white ware flat base. D 13,5 cm.
97. Bowl as No 93 D 11,5 cm.
98. Red washed nearly hemispherical bowl with base-ring. Part of lip missing. D 11 cm.
99. Red washed ware bowl with moulding round middle. D 10,5 cm.
100. Bowl as No 99. D 10,5 cm.
101. Bowl as No. 99. D 10,5 cm.
102. Bowl as No 99. D 10,5 cm.
103. Hemispherical red washed bowl with base-ring. D 9,5 cm.
104. Bowl as No 102. Part of rim missing. D 9 cm.
105. Bowl as No 102. D 9 cm.
106. Red washed plate. D 21 cm.
107. Plate as No 106. D 17,5 cm.
108. Plate as No 106. D 17,5 cm.
109. Red washed plate. Flat rim decorated with incised strokes. D 16,5 cm.
110. Plate as No 109. D 16,5 cm.
111. Red washed plate. D 14,5 cm.
112. Red ware bowl ovoid body decorated with vertical dotted lines in relief. H. 10,5 cm. D 8 cm.
113. Iron tool. L 14 cm.

113. Black ware perfume pot decorated with satyric face in relief.
114. Handle from rim to shoulder. Part of lip missing. H 10,5 cm.
115. Clay Roman lamp. L 9,5 cm.
116. Clay Roman lamp decorated with scallop-shell. L 9 cm.
117. Clay Roman lamp, decorated with ivy-wreath. L 10,5 cm.
118. Red washed ware lamp. L 8,5 cm.
119. Plain white ware lamp. L 9 cm.
120. Glass bowl green-yellowish colour with vertical parallel strokes missing. H 17 cm.
121. in relief, flat base. D 12,5 cm.
122. Bronze bowl with rounded base in the middle of the inside.
123. Glass conidal bowl with rounded base. Three incised parallel part three concentric circles. D 23 cm.
124. horizontal lines on the inside part near rim. D 13,5 cm.
125. The upper part of a bronze vase with spreading mouth. L 14 cm.
126. White glass bottle. Spiral line in relief round the body.
127. Lower part of a bronze vase. H 10 cm.
128. Spreading mouth, slightly flat base. H 8,5 cm.
129. Silver bracelet with overlapped links twisted round one another. L 5 cm.
130. Bronze sheet from wooden coffin. L 5,5 cm.
131. Varigated bottle, ovoid body, blue colour, tall narrow neck, ~~flat~~
132. flat rim. Base broken. Spiral yellow line round body and neck. H 8,5 cm.
133. Fragmentary silver ring.
134. Varigated amphoriskos with knobbed base, ovoid body, tall narrow neck with flat mouth. Handles broken. H 14,5 cm.
135. Loop-shaped bronze handle of a wooden bier. L 6 cm.
136. Varigated amphoriskos half part of body missing. H 8,5 cm.
137. As No. 130. L 6 cm.
138. Glass ring, white colour. (Fragmentary). L 3 cm.
139. Green glass spindle-whorl. D 2,7 cm.
140. Glass bowl flat base incised parallel horizontal lines round the inside part of the rim. D 10,5 cm.
141. As No. 134. L 10 cm.
142. Glass bottle wine colour, nearly cylindrical body with pointed base. H 16,5 cm.
143. Glass dark blue colour rod. L 16,5 cm.
144. Bronze chain. L 21 cm.
145. Limestone wheel of a chariot. Part missing. D 11 cm.
146. Bronze nail of bier. L 12,5 cm.
147. Wheel as No. 131. L 12 cm.
148. White sea-shell. L 16 cm.
149. Iron tool. L 14 cm.

135. Bronze vase with wide flat moulded base. H 5,5 cm.
136. The cover of the vase No 135. D 5,5 cm.
137. Hemispherical bronze bowl with rounded base. D 7,5 cm.
138. Small bronze round mirror. D 8,5 cm.
139. Bronze round mirror. D 18 cm.
140. Small round bronze plate. D 7,7 cm.
141. Bronze jug with flat moulded base. Cylindrical neck handle missing. H 17 cm.
142. Bronze bowl with rounded base in the middle of the inside part three concentric circles. D 23 cm.
143. The upper part of a bronze vase with spreading mouth. L 14 cm.
144. Lower part of a bronze vase. H 10 cm.
145. Silver bracelet with overlapped ends twisted round one another. D 5 cm.
146. Silver ring. D 2,5 cm.
147. Silver ring. D 2,5 cm.
148. Fragmentary silver ring.
149. Part of silver spoon. L 3,5 cm.
150. Loop-shaped bronze handle of a wooden bier. L 6 cm.
151. As No 150. L 6 cm.
152. " " " "
153. " " " 5,5 cm.
154. Bronze handle of vase. L 9,5 cm.
155. As No 154. L 10 cm.
156. " " " "
157. " " " 8,5 cm.
158. Bronze chain. L 21 cm.
159. Bronze nail of bier. L 12,5 cm.
160. As No 159. L 12,5 cm.
161. " " " L 9 cm."
162. " " " L 9,5 cm.

162. As No 159. L 6,5 cm.
163. " " " L 6 cm.
164. " " " L 7,5 cm.
165. " " " L 7 cm.
166. " " " L 6 cm.
167. " " " L 5 cm.
168. " " " L 6,5 cm.
169. " " " L 5 cm. Large bronze vase standing on three feet. Conical body with spreading mouth, two horizontal twisted handles on shoulder.
170. " " " L 5,5 cm.
171. " " " L 6,5 cm. H 32 cm.
172. Limestone ~~sarcophagus~~. The lid is in the form of a roof with "ridge-pole 6 cm. gables; the chest rests on four legs. The
173. Bronze sheet, rectangular, bent at right angles, pierced by holes for bronze nails; used as mountings to wooden coffin. L 15,5 cm
174. ~~chest has a border at each side, 1,00 m. wide~~ As No 174. L 16 cm., composed of wire ending in the head of a
175. " dolphin, L 17 cm. fin on each side of his neck and a globule
176. " in his mouth. L 16 cm. beyond the neck is a long sardonyx bead,
177. " terminate L 15,5 cm. end by a gold ring. D 3,5 cm.
178. " Gold ring with a ring-stone decorated with incised
179. " head. L 2 cm.
180. " Gold ring. L 13,5 cm. ~~in the inside part.~~ Ring-stone
181. " missing. L 11,5 cm., D 1,7 cm.
182. " Gold ring. L 11,5 cm. D 1,8 cm.
183. " Plain flat gold ring. D 1,5 cm.
184. " Gold female. L 21 cm. H 2,8 cm.
185. " Plain gold. L 18 cm. 19 cm.
186. " Bronze sheet. L 13 cm.
187. As No 187. L 11,5 cm.
188. " " " L 10 cm.
189. " " " L 9,5 cm.
190. " " " L 9,5 cm.
191. " " " L 9,5 cm.

192. As No 187. L 10 cm.
193. " " " L 9,5 cm.
194. " " " L 11,5 cm.
195. " " " L 7,5 cm.
196. " " " L 6 cm.
197. " " " L 7 cm.
198. " " " L 6 cm.
199. Large bronze vase standing on three feet. Conical body with spreading mouth. Two horizontal twisted handles on shoulder.
H 32 cm.
200. Limestone sargophagus. The lid is in the form of a roof with ridge-pole and gables; the chest rests on four legs. The chest has a pilaster at each side. L 1,80 m. H 97 cm W 51 cm.
201. 177 long pointed leaves in this gold.
202. Pair of gold earings, composed of wire ending in the head of a dolphin, with a fin on each side of his neck and a globule in his mouth. Beyond the neck is a long sardonyx bead, terminated at each end by a gold ring. D 3,5 cm.
203. Gold ring with black ring-stone decorated with incised head. L 2 cm.
204. Gold ring. Inscription in the inside part. Ring-stone missing. L 2,5 cm, D 1.7 cm.
205. Gold ring. Plain flat. D 1,8 cm.
206. Plain flat gold ring. D 1,5 cm.
207. Gold female statuette. H 2,8cm.
208. Plain gold strip. L 19 cm.
209. " " " "
210. " " " " 16 cm.



—

53.21

Mariam Tomb 104

E

(Polis Tomb Ia)

124


20-6

POLIS TIS KHRY SOKHOU

T.1A. T.1B.
8/12/1940

21-a



Approximate plan
of Polis T.I.A. and P.I.B.
Not all the vessels have
been marked or some
will removed before
Museum official visit
there.



21-6

Polis tis chrysodon Tamb 16

(guide to museum
photographs)



16
1a

Want pictures & b and?

Prominently two main groups

If I have not got anything
like all, in my sets Series

Dif. before since they are not in
order of inv. or of time

nu. A. 70-586
748 190

24

Point A Lined in 95 BC Απιστόνος Ραδιογένες

Kάσιος

" " " & 105 BC Βύανη Ναυκάσιος & Ραδιογένες

a lot of Τυμάνος

Photographs supplementary to those taken for Cyprus Museum, include all stamped jars, all lamps, all bracelets (save 2 nails)



4.12.40.

26-01

Tepeztla PoliceKamillidoreTajos & A.

Drawing made in a tent, the upper part by Pavlos, partly while George was digging; the lower part by George after Pavlos had to go back to Papito's drill with the volunteers.

From memory of this a copy sketch, in Papito's fashion, Pavlos makes the final drawing (17.7. in the file) omitting and adding a little. From this also, and sketch of other cave (8). Elias draws outline of cave + how rope

Tja. 98 workers

Maup. 210 workers

Iyos 150 workers

30. xpubu koup yax

31. xamirov ojix

Iyos 160 workers

Maup. 200 workers

Tja. 86 workers

32. xpiqir fanlyix

33. xamirov ojix

0m

0m

Maup. 265

Tja. 93


Iyos 153

53.

Maup. 194 workers

Iyos. 60 workers

Maup. 194 workers



92
91
90
89
88
87
86
85
84
83
82
81
80
79
78
77
76
75
74
73
72
71
70
69
68
67
66
65
64
63
62
61
60
59
58
57
56
55
54
53
52
51
50
49
48
47
46
45
44
43
42
41
40
39
38
37
36
35
34
33
32
31
30
29
28
27
26
25
24
23
22
21
20
19
18
17
16
15
14
13
12
11
10
9
8
7
6
5
4
3
2
1
0


Maup.
Tja. 10 workers
Tja. 235 workers
Iyos. Tajos 160 workers



081 562 K1 nov 002

o sequoyoxo xaxix in diao
6 Babo. 371 workers
new bracelet world 6 in
of skin help you bei Tajos


Iyos 157 workers
Tja. 115 workers
Maup. 205 workers



16. xpuso Aggihatam

32. xamirov ojix

32. xamirov ojix



Maup. 175 workers
Iyos. 235 workers
Tja. 165 workers

B ←

Maup. 90 workers
Tja. 52 workers
Iyos. 100

50. xamirov ojix
50. xamirov ojix
300
40
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60
61
62
63
64
65
66
67
68
69
70
71
72
73
74
75
76
77
78
79
80
81
82
83
84
85
86
87
88
89
90
91
92
93
94
95
96
97
98
99
100

'Odissea

'oth.

Odissea

Am

23

27.01

Cyrene March Jan. 1942

Polis vs Chrysokam "Typozata" Tomb 1A (See typed list)

1.) Rhodian stamped amphora

Ring covers broad with flat top with definite inward slopes. Tops of handles show considerable arch above angles (cf. with base Paros Tomb 1, when it lies sag or as of the handle.)

Left handle (not in mass plot) HH .275, .29

For Typa-

Typozata

Jan. 53.26

2 pieces

53.13, 14

Right handle HH .265 .281 (subtunis)

"Appodation"

H. 81

diam. 53.12

Capacity 26,100

2.) Rhodi stamped amphora

Bell in with hardly any flat top, but such as there is slopes in; not distinctly undercut. Top shows bulb growth. Right handle (not in mass plot) HH .216 & .23

[
also this is thicker, distinct but conjoining]

Typozata - quite clean

[?]

53.8

Also right HH ca. 215.22

"Appodation"

53.9

No rim seen on profile

H. 805 diam. 308 capacity 23,250

Opposite June 1942

24

27.02

Polaris Chgs. "Tip" Tab 1A

3. Rhodin stamped amphora, on walls gone

Rim convex band not sharply defined, flat to the slopes inward.

Toes on walls a part of neck gone, old bands no see-stamps or graffiti

Right handle

HH ca. 278 & 29

End "App." -

torvōos

Jan: 53.27

Epinθion

PH .78 ^{53.7} diam. .332

4. Rhodin stamped amphora, bottom gone

Rim a convex band with no very distinct flat top and no inward slopes.

Bottom gone, old bands

Right handle (top in un. phot.) HH. 26 - 278

'E[?] E3 a[?] o.-

(cf N. 200, 344)

pos

Epinθion

also right

Jan: 53.29

"Apposition

^{53.10}

graffiti  to right of lower att. of fab. handle.
Bottom ^{53.17} top of att. of handle

PH .716 diam. .331

5-9 are at present buried in the music yard

Entire 6 or 8 or 9 or 10 or 12 has one stamp on top of handle

See plot Vg Roll 53 - can probably make out which one

.. 5.48 53.15, 16 are said to be stamps 9 & 9 T 53.21 for #9
in next record

Cypress Mtn Jan - 1942

25

27.03

Polis Tis Chayood. Tool 1A

10. amphora with swollen neck, stamped on neck

Thin roughly flaring rim

Thin short everted ^{0.69 in} ~~everted~~ handles

Toe a knob with deep cavity, 0.33 in dia.

rim to toe a ring. 0.08 in dia. impressed by
firing.

near middle on side just below rim, stamped

A ^{wave} in circular field 65. 21

H .78 dia .314

11-19 buried in mussel agat

20. minima pittha

Rim flares downward somewhat from fairly sharp
ridge of spreading mouth. Broad handles. Peg
toe with rounded under side

Groove near handle .04 for top, perhaps inadvertent
Roughly made (dented under one low handle etc.)

of dull red clay with many dark white bits

H .298 dia .12

21. minima amphora

Rim

Toes in 2 steps

Finger impression at base of handles
Smooth finish



Buff clay with a few white bits - fine particles
of mica

Below the rim on side 3 short vertical stumps
in thin black

2 holes on one side of body (handles)

H .275 dia .121

upper Miss Jan 1942

26

27.04

Pots in Ovens - Tomb 1A

22. burnt in Miss grad.

23. red ware 2-handled pot

short flaring neck, the interior of which has 2 shallow grooves from wheel, the deepest one just under the rim (plain, flat-topped); 2 feet; the deep narrow groove at base of neck outside; 5 raised lines round shoulder made by application of handles - inside & outside handles should touch, where shows on wheel grooves

hard-baked missions red clay, purplish somewhat flattened (intact, no breaks to be examined)

24 white ware double-rimmed jar

2 concentric plain ^{vortex} rather thick rims, the inner standing a little over a centimeter high than the outer; horizontal grooved handles (one broken off); base rough, heavy fabric, roughly made and finished; clay with dirty buff surface; on the inside break shows reddish ring

25, 26 burned

Upper Miss. March 1942

39

27.05

Polis Tis Avayochas "Tiposet 1A (fig p. 26)

27.) plain gray narrow neck

pear flaring rim; ribbed band with
fing print at base; rough double mission
shoulder neck, covered by upper handle
attachment; grooves near base of neck, one a
crack, base ring
^{red and reddish buff}
red clay with numerous white bits and
some particles of mica

28-29 broad

30.) plain gray wide round neck

flat outlined rim with raised edge; eight ribs
handle rim to shoulder; ridged neck; base ring
rather shallow inside
^{rather from}
^{reddish buff and reddish clay with white}
bits

31-33 broad

34.) plain gray, short narrow neck

2 band bands come down outside; plain
missed line just above lower attachment; flaring
slightly flared rim (just broken away);
ring foot
red clay with yellowish buff; white
bits
remains of rim 7 adhering on side

Cypri Mure March 1942

40
27.06

Polis Tipajita 13A

- 35) red glazed narrow-necked jug
funnel top of rim with flat spout and raised edge;
thin band handle distinctly ribbed; low flared
base ring; pair of incised lines at base of neck,
an old wear top, covered over by handle
attachment
red clay, white bits, remains of somewhat
glossy red paint
H. 175

- 36) black glazed narrow-necked jug
plain thin band handle; flaring rim with pro-
jecting inner edge, rather heavy ring base,
shallow on inside, indented on sides
rather roughly made with beaded surface
dirty reddish buff clay with white bits, slightly
glossy (metallic in spots) black paint which
does not cover the lower part of the body

- 37.) glazed narrow-necked jug
spreading flat-top rim; band handle;
somewhat projected ring foot $\frac{1}{2}$; pair of grooves
round neck, covered over by handle attachment
pale buff clay, thin somewhat glossy paint, red
and blue brown

Polis Tyroglia Tomb 1 A

38.) plain jug, short narrow neck

plain flaring rim, plain band handle, ring base;
no incised lines
reddish buff clay, red and white bits (only surface
visible)

39. buried

40.) pinched rim jug

small neck flares to a wide collar forming a funnel
on interior; from the collar flares the open part of
the pinched rim (nose rim missing); band
handle sl. concave down outside ^{at about below rim}; ring foot
not distinct inside (rounded); pair of grooves
near shoulder, smeared over by lower handle att.

41.) lower part of small pit jar, full of plaster PH. 23

by stepped body, drip foot

dia. \approx 23

greyish buff clay, white bits

(much of the broken edge is an old break, so
the object was used in its broken state; it is
nearly full of calced dirty white powder)

42.) pear-shaped grid-glazed jug

spreading lip, smooth underneath & on also
~~overlapping~~^{opposite} edges overhanging; broad thin
band handle, 2 pairs of ribs down outside,
offset at base of neck; low ring foot, the body
flat interior with band having 3 concentric
bands ^{with much irregularity} with bands ^{with much irregularity} offset by

cyp. miss March 1942

42

27.08

Polis Tipyotes Tomb 1A

42. cont.) fine pale buff clay, with small bits but no mica; gray red (rusty) and black, with high metallic luster; under surface and inside of mouth also glazed; the glaze missing over large parts of the body, the ^{base} surface being partly of a deep ochreous yellow, apparently without regard to color the glaze is first red or black at this point

43.) red glazed narrow necking

spoon-shaped neck with funnel interior; broad thin band handle; ring foot with flared base
and groove at foot of flared; pair of metal
pins secured over by upper handle attached
day (only visible is small clips on foot) fine,
red; red glaze with high metallic luster

aprons
30
1, 5
very
thin
little

App. Musae March 1942

42

27.09

Polar Tropicolor Trich IA

42. cont.) fin pale buff clay, with small dark
iridescent spots; gray red (rusty) and black, with big
metallic lustre; under surface and inside of
mouth also grayed; the gray running over
large parts of the body, the ^{under} surface being partly
of a deep salmon yellow, apparently without
regard to winter the gray is first red or black
at this point

43.) red gray narrow marked jay

spoon-shaped neck with funnel interior, broad
thin band bridle; ring foot with plain head,
and groove at foot of plain; pair of metal
lions around base of upper bridle attached
clay (only visible in small chips on foot) fine,
red; red gray with big metallic lustre

spoon
1,530
1, very
thin
little

Polis T 1 B.

1. Plain white ware spindle-shaped bottle. H 20,5 cm.
2. Plain reddish ware jug with ovoid body standing on base ring, narrow neck, handle from rim to shoulder. H 19 cm.
3. Plain white ware spindle-shaped bottle. H 20 cm.
4. Red washed ware lamp. D 9 cm.
5. Red washed ware plate with base-ring. D 19 cm.
6. Red washed ware plate. D 10 cm.
7. Plain white ware spindle-shaped bottle H 15,5 cm.
8. " " " " " H 16 cm.
9. Six gold beads and 24 paste and glass beads.
10. 14 gold leaves.

4.12.40

Epagit Polis
Emelidon

Paphos 1 A"

20/II/41

Bronze fittings (bands bent round corners, and having nails)Found by Pavlos ^{in and at mouth of} ~~at mouth of~~ ^{or in this alcove} cleers near his numbers 31 (most of them here,
and 36, 38 (the large piece with the head Η only)Bronze mirror (diam. 18)Found by Pavlos more or less between his numbers 16 and 32 (appears
on his drawing made afterward in Paphos).⁴Bronze bands with upper part cut as for rim, lower part ending in tail

Found by Pavlos near his nos. 34, 35, outside the end of the rock wall

Bronze nails

Pavlos found many, apparently with the fittings described above

Red glazed grey, ht. 22 to diam. 165Pavlos found near his no. 29. It appears on his drawing made later
in Paphos(Pavlos attributes to tomb, but cannot place: bronze footed bowl, small
bronze hemispherical bowl, onion-shaped glass *unguentarium*, slender
mano glass tube with pointed tip.He does not recall in the tomb: eight types  of which the 4 here in-
cluded may then come from the classical tomb (George's no. 81)
21/II/41 Gray puts them with classical tomb.

The red glazed bowls and plates he attempts to place, and seems to recall quite definitely.

2

Of the large amphoras*; in states the ^{stamped} one without bottom came from between sarcophagi 52 and the wall, and was the first was he took out also that he recalls as from the tomb the stamped one with one handle missing. He does not think those 2 with double handles, or that one with heavy rim and long pointed tip came from the tomb, with there two couples one of the two with swelling in the neck, which happens to lie beside them.

George!

The sarcophagi, the large bronze vase, the bottom of a pot with plaster in it (which was next to the big vase) were on the same level, a bit above the floor.

The colored glass bottle with foot given is ^{his} no. 11, in the alcove next sarcophagi 53; in same alcove plain gold ring, his no. 1

The iron object he remembers well from the tomb, possibly from 5 of sarcoph. no. 53. He also remembers the ^{stone} wheels, and the piece of shell.

Neither Pavlos nor George really remember the small pithos on the amphorae with ringed top (55)



Placed by George on the original sketch, but not numbered: the large bronze vase, the large pear-shaped jug with peeling glaze, the headress, two lamps, which can be definitely identified as the large yellow one

* Further on stamped amphoras; there exists a possibility that two of them had been gathered in by the police some time previously. They are said to have offered two, and neither George nor Pavlos recalls whether such two ^{from outside the tomb} actually did join the collection brought to Nissia as a result of this expedition. Possibly the police themselves will know.

Plans of the Tomb

1.) Pencil drawing begun by Pavlos, added to somewhat by Georg, made either in the tomb or anyway at the time of digging apparently. Objects drawn by Pavlos are numbered, up to 54. Although no corresponding numbers were attached to the objects, the following have been identified by him with good probability:

- 16.) gold statuette 207
 - 30.) " fillet 208 207 or 210
 - 31.) bronze vase (jig nearly compleat, handle gone)
 - 32.) glass bowl with rather pointed bottom (although in drawing this looks more like #35 - he insists this was its place)
 - 32 again) glass ring
 - 33.) bronze basin, diam. 225
 - 34.) gold ring
 - 35.) glass bowl, plain, diam. .108
 - 38.) bronze vase, upper part, only, preserved
 - 39.) gold ring
 - 40.) small bronze jar without handles, with black stuff inside (nr. 052)
 - (45-47) he thinks were red glazed plates and/or red glazed bowls
 - 48.) bronze small flat plate, diameter .087
 - 50.) vari-colored glass amphoriskos, compleat save handles mostly gone
 - 51.) glass spindle whorl
 - 52,53.) sarcophagi, of which 52 brought to museum (53 was made of separate pieces)
 - 54.) silver or silver lead small bracelet (?) rings, 2 circles, bowl of spoon
- Pavlos identifies other objects not on this plan (see foregoing pages), and states that in sarcophagus ²⁰⁰ 52 there were the pair of gold earings with dolphin heads, the largest ²⁰² of the 2 gold fillets from the tomb and the gold signet ring ²⁰⁴ from which the stone (?) is missing.

For Georg's identifications on this plan, see p. 2

Not on this plan that a number of *fusiform* fragments are identifiable, but no ~~onion~~-shaped (1st century) ones.

2.) Plan made by Pavlos from memory and sketches, of which the museum seems to have a carbon copy (this in purple). This plan has no numbers, but nearly so many objects as 1.) but a few objects not on 1.), though still not the stamped jar without bottom next sarcophagus 52.

3.) Plan with outline, sarcophagi - one or 2 objects, in ink, many objects in pencil. Made by Elias from George's measurements and with his collaboration apparently. Note that the ring in the sarcophagi is wrongly placed according to Pavlos's account (he says it was in the middle where the band would have been). This plan includes the small chamber, B, opened and cleared entirely by George, with objects numbered; these have been washed, and consist of:

- 1.) *fusiform* fragment, early type, with glaze on lip; ht. .205
- 2.) squat jar, handle to narrow mouth.
- 3.) *fusiform* fragment
- 4.) red glazed lamp with high vertical ridge handle dia. .047
- 5.) shallow bowl, or plate, with rim dia. .19; ring foot; red wash
- 6.) bowl with incising near rim, ring foot, red wash or poor glaze, fine partly brown dia. .10
- 7,8.) *fusiform* fragments

Also from the chamber, beads bone and gold, gold leaves, and (high in case) pieces of colored glass fragment, rest of which was found in main tomb, acc. to George.

The original state of the chamber is among George's papers

Ten objects from this chamber appear to date from the 3rd cent. B.C.
probably early

The wares from the tomb have patches of desiccation and should be cleaned.

1.) (Pavlos's 31) ¹⁴¹ H. .17 diam. .162 rim diam. .074 Handle going with squat body, distinct neck, low ring foot, diam. .11 Flaring flat-topped rim, curving down ^{to} top and 2 below it and bits of the ring

2.) (Pavlos's ¹⁴² 33) H. ca. .05 diam. .226 Intact narrow pinched-out rim "in a ridge of the neck part & concave sides" plastic or basin

3.) (Pavlos's ¹⁴³ 38) PH. .14 diam. .152 rim diam. .098 upper part of apparently handle-less vase with globular? body, narrow neck, spreading down-turned rim

4.) (Pavlos's 40) H. .052 diam. .063 Intact small jar for cosmetics (?) no handle, ground & set off rim and foot contains about a heaping teaspoon full of some black stuff. More is adhering right up to the rim. Stick? to the bottom outside a bit of by ca. .01 x .08 See #14 for lid which fits

5.) (Pavlos's 48) diam. .088 H ca. .008 perhaps Intact Dish with raised rim like very shallow ash tray. Decorated with relief waves, 1, 2, and 3. Considerable traces of cloth along edge

(Bronzes, continued)

6) mirror (see p. 1 for position) diam. .182 unknown but
apparently a plain disk, slightly convex - convex
On convex side, traces here and there of a red powder,
bits of wood (?) and tiny particle of gold. Spots of candle-
green indicate this was uppermost in tomb. Few bits of
gold ^{and red powder} were on other side; most of this surface is smooth
and brownish, perhaps from plastering off of discarded surface
which remains round the rim.

7) (see p. 1 for position)

Intact

4 handles (?), objects having section of rim (less than
half the circle, of which the estimated diameters are between
.065 and .07) from the middle of which rises a stem
(round in section and ca. .003 in diam.) which curves
down and finally outward, tapering to a small knob or
a plain top. See photograph. Height .08 to .102

8.) (see p. 1) $\left\{ \begin{array}{l} \text{heads} \\ \text{walls} \end{array} \right. \begin{array}{l} \text{.083} \\ \text{.053} \end{array}$

, ranging in length from $.03$ to $.053$
2 about .13 long
The two long ones have mushroom heads, diameter a.02,
the others rather smaller flat heads. Slightly rectangular
in section. Wood adhering to many.


(Bronze, continued)


9.) (see p. 1)

Fittings presumably for wooden coffin(s?)

a.) 12 bands  bent about in the middle

to or next to a right angle, with six nails, also prong, placed as indicated. The nails are turned off neatly on the outside, and estimated $\pm .01$ on the inside. Total length of each of 8 ca. .20, of 4 smaller ones ca. .12, ⁽²⁾.14, and .16. Width of band .043-.033; less than .03 for one of the smaller ones. One of the large ones is broken in half, one of the smaller is broken - partly missing, from the rest a few of the projecting parts are clipped away, but on the whole they are in good condition although thin.


b.) plain band ca. .20 long, .045 wide, bent at right angles into a .08 and a .12 arm. Ends cut square, made from nails  thus, with large heads on the outside, of which 2 may remain, and the stubs of the spikes of them used. Fragments of at least 4 others. Thin foil like (a)

c.) 2 bands with fancy ends  , 3 prong nails indicated at each end arranged as small nail heads as in (a)

Bent at right angle somewhat off the center: length .08+.085 and .076+.098 (broken in 2) width .035, .036
Thin foil like (a)

d.) fragmentary larger band similar to (c.) found separately (see p. 1)
W. .071 PL as slightly bent, .24

(Bronze, 9d, continued)



A frags. possibly from the other end of the same object has a piece of the round part with a nail near its margin (not in a projecting piece).

10.) (See p. 2 for position, next description 52) $H .30$ Gain .323
Large bronze vase with 3 feet and 2 handles $\text{nd smaller dia. } .17$
 $\text{min diam. } .323$
 above a round bottom the body tapers also

to a flaring rim, turned down at edge

Marked feet on under side clear. Possible traces of lead
 for attachment, charm or handles than on feet

Intact except that
 feet and handles
 have worn off

11.) (not placed)

$P.H .098$ min dim ca. .044
 narrow rim base dia .065 body dia ca. .07
 small bronze footed bowl or goblet, top broken away, partly gone
 The stem is stopped with some fibrous(?) material, and may be
 hollow throughout.

12.) (not placed)

small hemispherical bowl, diam .078 H .044

(Brayton, continued)

13.) (not plant) dim .077Saucer with slightly incurved rim, concave under surface14.) (not plant) dim .058

Perforated rolled dish

quad. .013 - for fungi?

upper surface slightly concave

But this object is of course the lid of no. 4. Some of the black stuff adheres to its under side.

15.) (not plant)

4 rings with attaching spines  hummed backSee photograph for variation in the humming back

of the spines Rings .036 & .048 across,

16.) Linked pieces hanging from a ring of dim .025-

a ^{.008} wire ~~wire~~ ⁰⁰⁸ wire bend is bent into a ring, with the 2 ends extending another .037, where they are linked by 2 small rings to a piece .04 long, again linked by 2 small rings to a triangular piece  From one end of this long 2 wire piece .037 long each, joined by single rings; a hole for attachment also at the lower forward end. A ring hangs also from the other end of the triangular piece.

(January 1942)

10
29.10

Gold

- 207 Statuette Dugout found figure wearing palus? and carrying cornucopia H .028 Hollow, made with front and back mould. Stands on base, a deep scotia band. On back, at shoulders and ankles, looped bands for attachment. Hair pointing and looks indicated at back; draping only summarily. The figure stands with two rt. knee slightly bent, - the left also bent (show at side - behind), the left arm ^{cornucopia being held} seems to be dressed in chiton and bordered himation. Breasts sharp though draping

- 201 gold leaves (177 as counted in museum) L .023 E .05

N. B. - & beliefs written by yg stating that gold leaves were found both in sarcoph. 52 (200) (with earrings - ²⁰⁴ ²⁰³ fillet) and in sarcoph. 53 (with fillet [210]) The leaves 201 are both large & small, & original distribution was large leaves - may have been missed them. There does not seem to be a set of really small ones like 61 of St. Her. Tomb I However

greatest dim c. .04 across

- 202 gold earrings, dolphin heads with globules in mouth; base ^{base} ^{inner part with beads but fixed to head} mounted ^{top} of head a thick gold wire on which is strung a ^{hollow} ^{randomly (?)} bead between 2 circular ^{hollow} gold beads and, beyond them, 2 eye-like elements made of 2 disks joined together & held apart by thin gold wire; beyond outer "eye" bead another circular hollow bead, then the thick wire ends in a ring of 6 which is attached by a pin (missing in one) a bow of heavy gold wire which ends in another ring of which slips below 2 loops under dolphin's chin. No point to go through ear

(gold)

- 203 "gold ring with band ring stone size .w. widest band"
W .023 Finge opening not circular Edges of gold worn
to margin of the stone which shows whitish when engraved
See impression - looks better than actual gem!

204 "gold ring with inscription on inside part ring stone missing"
.02 x .023 Under where stone should be, some faint-like
stuff
written: FBDA (not quite as large as this)

205 "gold ring plain flat" dia .019
Band of beaten gold, narrow at back, spreading to a sort of
bezel - oval from whence band is bent off at ends

206 "plain flat gold ring" dia .015
Similarly made to 205, but smaller

(207 in beginning)

208. "plain gold strip" L .19 cm
209. " " " " " " ".195" →
210. " " " " " " .16
(end of the object is pointed near end at w,
small not very carefully made hole)



Trunk 1 B

- 9 "6 gold beads - 24 part. glass beads" The gold beads
were been string on inner side of a blue paste bead with eyes on it
beyond an blue paste beads with veins of dark color, green-
greenish blue glass, - dark red glass

29.12

Tomb I, B, 10 "14 gold leaves" - the bezel part of a silver ring with
double-wire shapt (bezal nearly circular, no dec. visible,
not closed)


35,01



132 128 119 124 121 130 129 124 123 125 127 126 133 131



... by following & to compare with two
from main tank 72, to approximate.



31-6



32-6



61. 1

024


f

33-6





34-6

Polis Ios Chrysochou { 207 Tomb 1A (quilt to mean photographs)








(169 appears twice . ?)



Polis Ios Chrysochorion Tomb 1A

(guide & museum photographs)



Nicosia, 11th January, 1941.

Dear Miss. Grace,

Many thanks for your letter. I am very glad my "Iraq" article interested you and I shall be very pleased to answer any questions when you visit us again.

reference to the


I am very sorry about the Lapithos Minoan vase. As you must have noticed I made full reference to your Expedition's discovery and intention to publish the find ~~in~~ a final publication. If I mentioned Casson it is because at the time I was writing only this reference was available. If however you consider that I did not give full credit to your discovery I express my deep regrets. As regards my Vounous publication it has not yet come out but it must be on the way as the final proofs were returned to England about a year ago.

About the Polis Tomb: The whole of the tomb group is in the Museum and is not to be included in the Emergency Measures although the jewelry has been placed in a safe store room. I am very sorry I gave no earlier information about the discovery, which appears to be much more important than I originally imagined. The material is all here and will be available for study as soon as cleaning, cataloguing etc. is completed. You may therefore call whenever it is suitable to you. The tomb contains 3 Rhodian amphorae, lots of other pottery, glass, bronze, jewels etc.

My wife and myself were very sorry indeed to have missed you. We shall be delighted to visit you next time we are in the neighbourhood.

With all good wishes from both of us,

Yours truly,



P.S. I shall be very glad, in future, to give you immediate information about discoveries connected with Hellenistic pottery.


Tomb in Polis, in the field of Erato Kanelidis, "Topogito"
 discovered 28/xi/40, information of Public Works foreman to police
 apparently in the air raid precaution trenches

- 28/xi/40 notification to Police Inspector of Paphos from P. Sgt. 699 R. Chau; ^{had}
 one ~~old~~ ^{new} about 2 digits ^{long} & 2 cm. of which was on "mon 25" taken
² ^{27.80%} can be made out
 from Paphos curator to P.D. recorded in memo, with remark
 that he has offered sending the curators to supervise clearing
- 29/xi/40 memo that police inspector in Paphos informs the tomb is "rather important"
 necessitating night watching. Group to go to Polis - supervisor.
 Pavlos has been ordered to stop work until Group comes, G. will come 3/xii/40
- 2/xii/40 date on
 " Pavlos's purple (carbon?) drawing. Odd, because he is supposed to have
 done this in Paphos (stamped as received 12/xi/40)
- 10/xii/40 letter to Miss Antigone from Logos Philopon, stating Pavlos went to
 Polis Nov. 29 & excavated tomb found when ARP trenches were being
 constructed in "Depositor" area. Tch to supervised up to Dec. 5,
 when an assistant of the Central Museum came and instructed
 That shelter is enclosed, - such a such gold was found. ^{after inspection} Pavlos
 hopes finds will go to Paphos Museum. (stamped as received)
 12/xii/40
- 14/xii/40 Telegram to P.D. from Erato Kanelidis, not permitting further
 excavation in his land.
- 9/xii/40 statement from foreman of Works ^{Elias Longos} (now he was working in Kanelidis field)
 digging trench, found ancient tombs, immediately informed police,
 knew man came who worked in the. Showed him where the
 were other tombs.
- 17/xii/40 set on to plan drawn by Elias, signed by Group
- 16/xii/40 Form 9 filled out by Group with account of excava. while he was
 there. Went 3/xii/40. Statement of what Pavlos had dug.
 Brought also objects from another small tomb which he found in the
 police station. State that he examined 3 tombs in field of a
 carbonarius, but they had been worked already.
- 17/xii/40 Lists of objects from Tomb # 1A, 1B, 2 (pots with stoneware etc.)
- 14/1/41 bath 6/1 missing from own. 24/1/41 What do you want to know to / 10/1/41
 10/1/41 elias from Elias Longos for bath

37.02

Pavlos's story, wed 20/II/41

Policeman George from Polis comes to Pavlos and reports that in digging ARP trenches, the (public works) people cleaned out a cave which was ^{at} ~~into~~ across by the trench.



This had ten black glasses and ten rings with women on them. (One of these Pavlos dug himself, cleaning afterwards)

And that the hole into another ^{cave} appears in the bottom of this trench. Mr. Logos telephoned to Dikaios, who says Pavlos to go immediately ^{for gold in capsule}. He went on a Friday evening, worked Saturday till noon, then it rained Sunday went all day, found ^{not} the gold (right outside before then, very night). Monday morning, telephoned to Mr. Logos but he was in Nicosia, returned to cave. Now Mr. Dikaios called in by telephone: what is going on in Polis? - Found this - Stop until George comes - Next day (Tuesday) George comes.

When P. first went in, looked about, saw door, measured from large stone ^{tower}, disappearing into earth below. The sarcophagus 52 showed which he went right to (and perhaps then ran up ^{to open other with - get things out}). also now

holes in the cover under the sand.

37.04

Inside sarcoph 5-2 (broken top) half full earth. Found gold, no bones.
The earings - fillet (no leons in this sarcoph.) together at one end,
the ring in the middle worn finger old b.

The burial & alcove w. nos. 30-31, because little earth there,
wished to clear it & make the place as deep. No bones there
(Bones among plates 17-27. Big oss^ulum bones near sarc. 5-2, btd. 33
- 51.) Possibly Mosaic floor without handle was with 1-15.
not much earth under them. Alcove w. 36-43, gray clay,
no drew. Before gray came, clay in Sarcoph 5-3 - found gold.
Didn't finish drawing because had to go back to Volunter's
drill.

Polis Tis Chrysochou Tomb 1B

(given to museum photographer)



No. 100/39

Telephones:

D/Ants. 397.
Office. 61.



DEPARTMENT OF ANTIQUITIES,
CYPRUS.

Nicosia, 19th January '42

38.01



Dear Miss Grace,

I beg to enclose copy of the analysis of the black substance found in the bronze bowl from Polis prepared by the Government Analyst.

Yours truly,

Miss V. Grace,
Pennsylvania University,
Museum Expedition to Curium,
Episkopi, Limassol.

ANH.

38.01

No. 100/39



DEPARTMENT OF ANTIQUITIES,
CYPRUS.

Telephones:


D/Ants. 397.
Office. 61.

Nicosia, 19th January '42

Dear Miss Grace,

I beg to enclose copy of the analysis of the black substance found in the bronze bowl from Polis prepared by the Government Analyst.

Yours truly,



A handwritten signature in cursive ink, appearing to read "H. H. Munro".

Miss V. Grace,

Pennsylvania University,
Museum Expedition to Curium,
Episkopi, Limassol.

ANH.

38.02

COPY.

No. 5/42.

Tel. No. 2

GOVERNMENT LABORATORY,

MEDICAL DEPARTMENT,

Nicosia, 19th January, '42.

Director of Antiquities,

Nicosia.

X

X

X

X

The sample consists of a mixture of earthy matter, composed essentially of sand, calcium carbonate and organic matter, with oxide of copper.

(sd) H. Atkinson


Government Chemist.



39-6

Polis tin Chrysoken Finds 18.

(given to museum photograph)



• 384 10

POLIS TIS CHRYSOCOCHOUS "TIPOZITA" TOMB IB

cleared by Cyprus Museum, Dec. 1940

2
1:151
1:73
1:77
1:78
1:74
1:5

1:5

Type III, ann. hilt bunch
S. fragment - Cf. SB p. 32, fig.
45, and that mentioned
PIT and red paint.
Diameter 8.2 cm. probably
end beginning of red
But cf. MAT. E 90, ill. p. 412,
in which 8 thin, long green
leaves red paint.



9

1:3.6



part of 10

1:1

5 (plate)
6 (bowl)

part of 10 (gold
leaves)



42-b

Cypres Mtns Jan. 1942

27

43.01

Polis Typoglin Tomb 1 B Notes supper & bus. list
and photographs

1.) Partly glazed *magnatane*, type of Curn P 15-23

Light reddish buff clay with numerous bits. Body not -
white. Hard fairly smooth surface. Thin brown glaze
with some lusters dripping down from mouth and neck
as far as visible.
Foot body clipped.

2.) Squatting with edge inside mouth, (made by construc-
tion of neck) - ring foot

Tinclad band handle

Coarse clay, many bits, mottled brick red to greyish
brown. Surface rough, esp. lower part, where much
scratched.

Interior saw for cracks

3.) Fus. unglazed.

Body completely naked flaring lip. Stem shows twist
glasses. Foot distinct but not carefully modelled.
Under side rough for wear.

Handle

4.) Red glazed lamp with raised vertical bands Type ^{Fig. 11, 12}

See photo. Glaze round sides of top, just below edge
I raised circular round center bottom. Side of handle very
roughly finished.

Flame profile by off clay with some white long white bits.

Red glaze quite lustrous on body a wavy, not on handle
nearly considerably blackened; a streak of blackening goes
under it to bottom of lamp.

Handle

L. .092 (without H) W. .047 H : 031 (without
handle)

Cyprius Mus Jan 1942

28

43.02

Polis Typology Tomb I B

5) ^{Same} painted
Same with banded rim; plain center, ring foot

Rim a convex band with no outward projection but
offset from interior; wheel marks give faint effect
of rifling.

Fine light red clay. Red paint without brush wash
and dripping on outside = H.b. Prob. the last
wheel it does appear (as on body of #4) is due to
polishing of surface? not wash of paint.

6) Same painted, incising bowl, ring foot
^{H. 10.3}
Low bowl, not very marked incision

Buff clay varying in tone

Paint comes visible - most of outside; red except
first band on side; some last in a thin line on outside.

7) Fins. unglazed, plain ware

Rim flares down outward, also on stages inward,
from ridge

Plain glaze, too not set off from stem. Under side
rather concave - rough from wheel.

Clay with white bits, with stiff & red

8) Fins. Unglazed, plain ware

Knocked down - flared rim. Single flaring too rough
underneath. Traces green on stem.

Buff clay, a few white bits.

9-10) in sq. So drawn in other notebook. Unfort. no paper
stated as 5 types of bases, but as I recall they are
of the "Later" type, clay.

J.A.R. Munro: Excavations in Cyprus, 1889. Second season's work - Polis Te_s
Chrysochou.

Journal of Hellenic Studies, x1, p. 1-60

on p. 34: The amphorae with inscribed handles: Some of the
most legible read:

Εὐκράτεον with caduceus (K.53)

-Ετι Τρισαγόπα Δροπογοπίον (K.53)

Ὑγαστιώνων with caduceus and

ται Τιβογίνων Υακίνθιν (K.53)

ται Απιστογάριον Υακίνθιον (M.3).

One from B. 4 bore simply a cup (caudex).

p. 35, fig. 5: 2 jars (1 one looks Rh(?) There is a 3rd of eastern type,